Rockwell International SUPPORTING DOCUMENT **Energy Systems Group** REV LTR/CHG NO SEE SUMMARY OF CHG S/A NO. PAGE 1 OF TOTAL PAGES NUMBER GO NO. 07704 44650 8 NC N704TI990034 8 PROGRAM TITLE Decontamination and Disposition of Facilities Radiological Survey Results - Release to Unrestricted Use, SRE Region VIII DOCUMENT TYPE KEY NOUNS Technical Information Decontamination ORIGINAL ISSUE DATE **APPROVALS** DATE REL. DATE 5-13-83 1/2 R. J. Tuttle MAIL ADDR B. F. Ureda BU7. Uheda PREPARED BY/DATE DEPT blace C. C. Conners Cc Com 779 T034 J. M. Marzec W. R. McCurnin W. R. Makerman 5/4/83 M. E. Remley My (semiley "imay 53 IR&D PROGRAM? YES INO IX IF YES, ENTER TPA NO DISTRIBUTION ABSTRACT MAII * NAME

ADDR **NB02** * C. C. Conners J. M. Harris T055 T143 J. M. Marzec T020 W. R. McCurnin **NB13** * M. E. Remley * R. J. Tuttle * B. F. Ureda **NB13** NR05 T034 * J. H. Wallace

The results of the radiological survey for Region VIII of the SRE facility are described. All survey results are below the applicable limits, indicating that this area may be released for unrestricted use.

RESERVED FOR PROPRIETARY LEGAL NOTICES

THIS REPORT MAY NOT BE PUBLISHED WITHOUT THE APPROVAL OF THE DOE OFFICE OF PATENT COUNSEL

This report was prepared as an account of work sponsored by the United States Government. Neither that United States nor the United States Department of Energy, nor any of their employees, nor any of their contractors, subcontractors, or their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness or usefulness of any information, apparatus, product or process disclosed, or represents that its use would not infringe privately owned rights.

0057Y/reg

* COMPLETE DOCUMENT

NO ASTERISK, TITLE PAGE/SUMMARY

OF CHANGE PAGE ONLY



. N704TI990034

PAGE . 2

CONTENTS

		Page
1.0	Introduction	3
2.0	Surveys and Results	7
3.0	Conclusions	8
	TABLES	
1.	Contamination/Radiation Limits	5
2.	Survey Measurement Requirements	6
	FIGURES	
1	SRF Facility	4




· N704TI990034

PAGE . 3

1.0 INTRODUCTION

This document covers Region VIII of the SRE facility (Figure 1). The area consists of the paving to the south and west of Building 143 to approximately the enclosure for T1/T2 and T3 pits. It includes the drainage channel along the southwest to south edge of the paved area.

N704TI990034



SRE FACILITY



NO .

N704TI990034

PAGE .

The contamination/radiation limits for unrestricted use that were applied in decontaminating this area are shown in Table 1 and the requirements for survey measurements in each region are shown in Table 2.

TABLE 1
RESIDUAL RADIOACTIVITY LIMITS
FOR RELEASE FOR UNRESTRICTED USE

	Total Removal			
Surfaces				
Alpha	100 dpm/100 cm ² 20 dpm/100 cm ²			
Beta	0.1 mrad/hr at 100 dpm/100 cm ² 1 cm through 7 mg/cm ² absorber			
<u>Soil</u>	100 pCi/g gross detectable beta			

NO . N704TI990034

PAGE . 6

TABLE 2 SURVEY MEASUREMENT REQUIREMENTS

Region	Removal Contamination	Surface Radiation	Soil Samples	Concrete Samples	Water Samples
I	Х	Χ	Х	X	Х
II	X	Χ	X		
III		Χ			
IV	X	X	X		
٧		X	Χ	Χ	
VI		Χ	Χ		
VII		X	X		χ
VIII		X			
IX	X	X	χ		
χ	X	Χ	Χ		
041	X	X			
063	X	χ			
143 Offices	X	X			
143 High Bay	X	X	Χ	X	X

Measurements of removable contamination are omitted from those areas that consist solely of soil or asphalt-paved surfaces



N704TI990034

PAGE . 7

2.0 SURVEYS AND RESULTS

A. SURFACE RADIATION

At the conclusion of the D&D effort, a survey was conducted using three survey instruments, a Technical Associates Model CP-7 ion chamber, a Ludlum Model 12 with a thin-window pancake GM detector, and an Eberline Model PRM-5-3 low-energy gamma detector. The Ludlum GM detector and Eberline low-energy detector were used for their faster response and audible output. The CP-7 showed an average reading of 0.04 mrad/h for Region VIII which is a typical reading in all uncontaminated areas at Santa Susana. All readings with the CP-7 were below the Table I limit of 0.1 mrad/h. Surveys were performed as specified in N704TP99008, "Radiological Survey Plan, Support of D/D Program Operation at T143, SRE," R. K. Owens. Copies of survey results and data sheets are retained by Radiation and Nuclear Safety.



. N704TI990034

PAGE . 8

3.0 CONCLUSIONS

In each type of test performed, all samples indicated levels less than those limits prescribed by the Decontamination and Disposition of Facilities Program for release for unrestricted use.

All appropriate surveys indicate that current existing radioactivity in the area is below the applicable limits for release for unrestricted use.